



ENCLOSURE THERMAL TESTING HEAT REMOVAL IN THE REAL WORLD

Switch to perfection **RITTAL**

I. INTRODUCTION

As a leading manufacturer of enclosure solutions, Rittal is frequently asked to make recommendations for cooling cabinet-installed active components supporting network and server operations. With a host of sometimes contradictory information being published, the tests were performed in an active data center, with active components and well established operational parameters. This "Real World" test program provides results for how entire facilities – servers, enclosures, climate control, etc. work together to remove heat generated in these spaces.


With an eye towards "Best Practices", the purpose of the testing program is to provide temperature data from a variety of enclosure and facility configuration variables; set-ups commonly found in today's data center environments. While the data indicates certain designs perform better than others, each reader is left to draw individual conclusions as to the 'Best' cooling solution based on specific site and end user criteria. Finally, this paper will provide recommendations and suggestions, based on empirical data, for climate control and enclosure design and selection.

II. HEAT ON THE RISE

Cooling and heat removal, in a data center and at the enclosure level, have quickly become the most critical factors in data center design. With the exponential increase in deployed servers, heat loads have almost quadrupled in the last seven years. While early sites were designed to support 50 – 100 watt/sq.ft. loads, today's facilities are required to support up to 200 watts/sq.ft. and greater. Can 350 watts/sq.ft. be far behind? Worse, these increasing loads are often concentrated in limited floor spaces in the data center.

In the last 2-3 decades, the unparalleled growth of computing power and information storage has been staggering (See *Figure 1*). The first data facilities were designed to handle large mainframe systems. IBM, DEC and others were the leaders in this field, building more powerful systems while keeping to a relatively fixed footprint. Some of these systems were liquid cooled, with chilled water (usually from building supply) channeled through mainframe hardware. With the advent of the microprocessor, chips took over as the brains of computer systems. Simultaneously, storage moved from tape and disk to much smaller form factor media. As computational power increased and chip size decreased, water was phased out, replaced by ambient air as the primary cooling medium. Existing facilities were not ready to handle these growing heat loads.

Climate control requirements in the data room impacted other areas of data room design. Computing power and storage needs grew as the way we do business progressed. Eventually, the Data Center was born. And then rack mount servers were introduced. Originally thought to be for standalone applications of one or two enclosure-based systems, the rack mount server quickly evolved to be THE enterprise. Servers could not be deployed quickly enough to support the growing demands of Information Technology. Data facilities



| Year | BTU/Hr | Watts | Comments |
|------|--------|-------|------------------------------------------|
| 1990 | 500 | 145 | Early Token Ring and Ethernet Components |
| 1995 | 1200 | 348 | Tower or Desktop PC's |
| 1997 | 15000 | 4350 | 1st Generation Rack Mount Servers |
| 2000 | 22000 | 6380 | 2nd Generation Rack Mount Servers |
| 2003 | 45000 | 13050 | High Density (1U) Rack Mount Servers |
| 2005 | 70000 | 20300 | Blade Servers and Future |

Figure 1

were quickly populated with hundreds of enclosures supporting ever-increasing numbers of rackmount servers and storage devices. As these were deployed in greater numbers, existing spaces could not handle their specialized physical plant and environmental demands. Power and cable management, access for service, room for expansion and storage systems and even disparate mounting hardware and specifications all contributed to the problems. And the room just kept getting hotter:

Old data facilities and new construction centers have addressed many of these issues. Higher raised floors, upgraded power distribution, redundant sources for power and connectivity, enhanced cable management and of course improved climate control have all contributed to greatly enhanced reliability and overall uptime.

But when addressing specific cooling issues, there is a potential conflict; a conflict over enclosure airflow paths and the best way to remove heat. Rackmount server manufacturers require front to rear cooling across servers, best accomplished with the traditional server cabinet – fully perforated doors front & rear with >65% openings. However, there remain proponents of alternative cooling methods, most commonly bottom to top (chimney) airflow paths, some using solid instead of vented front doors. There are also differing solutions using fans to remove and redirect hot air out of and away from enclosures. Even fan quantity, capacity and placement are debated.

The test protocol and results described in the following sections are designed to evaluate various enclosure configurations and their effects on heat removal and dissipation. The following sections review site and enclosure layouts, the testing protocol, components evaluated and test results. A brief analysis is provided along with suggested installation and climate control guidelines



Figure 2A: Row with test cabinets



Figure 2B: Hot aisle



Figure 2C: Test cabinets with roof fans

III. TEST SITE & ENCLOSURE REVIEW

The thermal test program was designed to measure enclosure cooling capabilities in an active data center. The following variables were tested:

■ Enclosure Door Configuration

- Vented
- Solid
- Partial Vent (Front &/or Rear)

■ Floor Tiles

- Perforated
- Solid (In front of enclosures)

■ Enclosure Fan Placement

- Rear Door
- Bottom
- Roof (w/solid roof)

■ Cabinet Heat Load – 2100 watts or 5500 watts

Thermal dissipation tests were conducted on three enclosures in the data center.

The enclosures were configured identically for each test scenario. The test enclosures were part of a larger row of cabinets in the room (See Figure 2A). All three enclosures were bayed together with no internal dividers (except for the tests using divider panels). A sidewall was installed between the third test enclosure and the adjacent active cabinet and the rest of the row. Component installation, wiring, blank panels and related hardware were identical for each test enclosure.

Data Center Parameters:

- Approximately 25,000 sq.ft. raised floor space
- 18" Raised floor plenum height w/17" clearance floor to tile bottom
- 12 Foot Raised Floor to Ceiling height
- Open Ceilings
- Hot Aisle/Cold Aisle Orientation
- CRAC Units located on inner walls
- Overhead (copper and fiber connectivity) and under floor (copper and power) cable entry




Figure 3: Data Center Layout

A series of tests was conducted with 2.1KW heat loads per enclosure. Thirty-one 1RU Dell servers were installed from the 5RU to 35RU positions in each enclosure. Power to all servers was provided by three vertical and one rackmount powerstrips, the powerstrips equipped with load monitoring capability.

See Table 1 for complete list of 5.5kW Testing Configurations.

To create a greater heat load, eight servers were removed from each test enclosure and a Load Bank placed in the vacant space. Each load bank was set to provide 4KW of heat. A total of 5.5KW per test enclosure (servers + load banks) was achieved. Rackmount servers continued to draw power from the powerstrips; the load banks were serviced by two 20amp circuits from under the floor per load bank. Each load bank was installed in the lower section of each enclosure to simulate installation of a larger rackmount server (i.e. HP7410, Proliant ML750, Sun V880z). Standard industry practices place heavier components lower in an enclosure to provide ease of access and reduce chance of tip-over. These larger units produce significantly greater heat loads than 1 – 3 RU systems, concentrating the heat in the bottom section of an enclosure.

See Figure 4A and 4B above for details of active components installations.

19" Rackmount blank panels were installed in all unused rack spaces on the front mounting rails in all three enclosures. To support installation and operation of bottom mount blowers (when tested) the first three RU were left open for all tests. All power strips were installed in the rear of the enclosures, vertical strips positioned outside the 19" mounting plane and the rackmount strip in the 4RU position from the bottom (behind and above bottom mount blowers).




Figure 4A: Front of test cabinets




Figure 4B: Thermal probes on the rear door of the cabinet



Thermal Testing Protocol: Table I

Listed below are the various cabinet, fan and facility configurations tested. Approximate Cabinet Heat Load 5500Watts

| Test Number | Front Door | Rear Door | 19" Rail Location | Floor Tile | 2 x Rear Fans | Bottom Blower | Divider Panel | Roof Fan | Test Start Time | Test End Time | Total Hours Tested |
|-------------|------------|-----------|-------------------|------------|---------------|---------------|---------------|-----------|-----------------|---------------|--------------------|
| 1 | Perf | Perf | Front | Vented | – | – | – | – | 2:30PM | 11:05AM | 20.58 |
| 2 | Perf | Perf | Front | Solid | – | – | – | – | 11:30AM | 11:15AM | 23.75 |
| 3 | Perf | Perf | Front | Vented | Installed | – | – | – | 11:35AM | 12:30PM | 24.92 |
| 4 | Perf | Perf | Front | Vented | – | Installed | – | – | 1:00PM | 11:30AM | 22.50 |
| 5 | Perf | Perf | Front | Vented | Installed | Installed | – | – | 12:30PM | 11:30AM | 23.00 |
| 6 | Perf | Perf | Front | Solid | Installed | Installed | – | – | 12:40PM | 2:30PM | 97.83 |
| 7 | Perf | Perf | Front | Solid | – | Installed | – | – | 3:30PM | 12:30PM | 21.00 |
| 8 | Perf | Perf | Front | Vented | – | – | Installed | – | 2:00PM | 12:10PM | 22.17 |
| 9 | Perf | Perf | Front | Solid | – | – | Installed | – | 12:05PM | 12:05PM | 24.00 |
| 10 | Solid | Perf | 4" Back | Solid | – | – | – | – | 4:00PM | 11:00AM | 19.00 |
| 11 | Solid | Perf | 4" Back | Solid | – | Installed | – | – | 12:15PM | 3:00PM | 26.75 |
| 12 | Solid | Perf | 4" Back | Solid | Installed | – | – | – | 3:45PM | 12:00PM | 20.25 |
| 13 | Solid | Perf | 4" Back | Solid | Installed | Installed | – | – | 12:30PM | 11:30AM | 23.00 |
| 14 | Solid | Perf | 4" Back | Solid | – | – | Installed | – | 5:10PM | 11:30AM | 18.34 |
| 15 | Solid | Perf | 4" Back | Solid | – | Installed | Installed | – | 12:30PM | 2:20PM | 25.83 |
| 15A | Solid | Perf | 4" Back | Solid | Installed | – | Installed | – | 12:15PM | 12:10PM | 23.92 |
| 16 | Solid | Perf | 4" Back | Solid | Installed | Installed | Installed | – | 12:45PM | 10:30AM | 69.75 |
| 17 | Solid | Solid | 4" Back | Solid | – | – | Installed | Installed | 11:45AM | 10:30AM | 22.75 |
| 17A | Solid | Perf | 4" Back | Solid | – | – | Installed | Installed | 2:30PM | 11:15AM | 44.75 |
| 18 | Solid | Solid | 4" Back | Solid | – | – | – | Installed | 11:40AM | 12:15PM | 24.58 |
| 18A | Solid | Perf | 4" Back | Solid | – | – | – | Installed | 10:40AM | 10:05AM | 23.42 |
| 19 | Solid | Solid | 4" Back | Solid | – | Installed | – | Installed | 12:50PM | 10:15AM | 21.42 |
| 19A | Solid | Perf | 4" Back | Solid | – | Installed | – | Installed | 10:40AM | 10:15AM | 23.58 |
| 20 | Part Vent | Solid | 4" Back | Solid | – | – | – | Installed | 10:40AM | 10:30AM | 47.83 |

Dimensions and initial configuration for the test enclosures:

- Height: 79"/42RU Width: 24" Depth: 40"
- Fully perforated (67% open) doors – Front and Rear
- Vented Roof with cable entry slots
- 2 Sets Vertical Mounting Rails – EIA Standard Hole Pattern
- Front mounting rails approximately 1.5" off front door.
- 19" Mount Blank Panels installed in unused rack spaces on front rails
- Perforated floor tiles in front, solid tiles behind each enclosure
- 18" x 17" cutout in front floor tile under each cabinet + 2" x 4" diameter cutouts under cabinet back
- 23 1U Dell Servers in the 13U - 35U rack location
- 1 load bank providing 4kW of heat

IV. TEST & MONITORING SYSTEM

Detailed monitoring, data collection and logging were essential to insure the results accurately reflected actual operating conditions. The Rittal CMC-TC Enclosure Monitoring System was used for these tests. The CMC-TC system provided real-time monitoring of the various temperature points in each cabinet, recorded the data for each test period for each enclosure and provided trend data to insure no transients occurred during each test.

Each test enclosure was equipped with a CMC base unit and Input/Output (I/O) modules. Twelve temperature probes were connected to each CMC in each enclosure. Each CMC was connected via the onboard 10BaseT port to a hub, creating a standalone monitoring network for the test enclosures. Using SNMP, the CMC's communicated all test data to a central computer for each test. The monitoring computer was set up to capture and store data in a separate file for each CMC. Trend data for each CMC was also stored in individual files.



Figure 5
■ – denotes thermal probe locations

Test probes were placed in the following locations:

- 1:** Under floor in front of cabinet
- 2-7:** Front, at server air intakes
 2-@ 5U, 3-@ 12U, 4-@ 20U, 5-@ 25U, 6-@ 30U, 7-@ 35U
- 8-11:** Centered on rear door
 8-@ 6U, 9-@21U, 10-@31U, 11@ top
- 12:** Center of roof

Probe Placement Notes:

Front probes were attached directly to the servers to measure inlet air as it entered the units. When servers were moved back (4") for solid door tests, inlet temperature probes moved with the servers. Please see *Figure 6* for a schematic view of the CMC monitoring setup.

Rear probes (1 – 4) were secured directly to the rear door and not at server discharge. This location recorded discharge temperature of exhaust air as it vented into room spaces.




Figure 6



V. TEST PROTOCOL

At the start of a test, each enclosure was set up with the appropriate configuration. All servers and load banks were constantly kept on, with the servers running a program to continuously exercise the processor. Rackmount servers were installed using Dell installation brackets in accordance with manufacturer's specifications. After set up was completed, all doors were closed and the test begun. Each test ran for at least 20 hours, some ran over two days. The computer was configured to capture data every two minutes from each test probe (36 total) to create trend logs. These logs verified operating conditions during the span of each test, insuring there were no transients, i.e. door opening, fan failure, facility condition.

At the end of each test period a final set of temperatures was recorded and the test was stopped. Please see *Table 2* for a sample of the test data sheet. Temperatures were averaged across the three enclosures. The enclosures were set for the next test configuration and the process was repeated; data recorded at the end of each test run.

At the completion of all tests, data was recorded on a master spreadsheet for the three main enclosure configurations tested:

- Server Cabinet with fully perforated doors front and rear
- Equipment Cabinet with a SOLID front door and PERFORATED rear door
- Equipment Cabinet with SOLID front door; solid or perforated rear door AND roof mount exhaust fans

The data collected shows results for each test and compares similar cabinet configurations with one or two different test variable (ex: rear fan vs. roof fan, perf door vs. solid door). Results for all tests at 5.5KW heat loads are provided in the following tables and charts.

Sample Data Sheet: Table 2

Test Number: 20 **Approx Heat Load:** 5500 Watts
Cabinet Configuration: Partial Vented View Door - Front
 Solid Door - Rear; 2 x 550 cfm Roof Mount Fans
 Solid Floor Tiles - Front

| Temperature Probe Locations | | Average Temperature of cabinets during 2 day testing - ° Fahrenheit | | | |
|-----------------------------|-----------------------------------|---------------------------------------------------------------------|----------------|----------------|---------------------|
| | | Cabinet 1 Temp | Cabinet 2 Temp | Cabinet 3 temp | Average For Test 20 |
| Air Intake | | | | | |
| 1 | Under Floor - In front of Cabinet | 68.0 | 68.0 | 66.2 | 67.4 |
| 2 | Front - Server @5U | 68.0 | 68.0 | 64.4 | 66.8 |
| 3 | Front - Server @12U | 68.0 | 69.8 | 68.0 | 68.6 |
| 4 | Front - Server @20U | 69.8 | 71.6 | 68.0 | 69.8 |
| 5 | Front - Server @25U | 71.6 | 73.4 | 68.0 | 71.0 |
| 6 | Front - Server @30U | 75.2 | 77.0 | 69.8 | 74.0 |
| 7 | Front - Server @35U | 75.2 | 73.4 | 71.6 | 73.4 |
| Air Discharge | | | | | |
| 8 | Rear Door - @6U, Center | 87.8 | 77.0 | 77.0 | 80.6 |
| 9 | Rear Door - @21U, Center | 100.4 | 100.4 | 98.6 | 99.8 |
| 10 | Rear Door - @31U, Center | 93.2 | 93.2 | 86.0 | 90.8 |
| 11 | Rear Door - Top, Center | 93.2 | 87.8 | 86.0 | 89.0 |
| 12 | Roof - Center | 93.2 | 87.8 | 84.2 | 88.4 |

Temperature results represent an average of all temperatures recorded at each probe every 2 minutes

Installation Notes:

- Vented floor tiles were only installed in front of cabinets with perforated front doors .
- Solid tiles were used with solid doors to insure airflow was directed into enclosures and not dissipated in front of enclosures.
- Front 19" mounting rails were recessed 4" from front doors when solid doors were installed to insure a sufficient column of air was available to server intakes.
- Two rear door mount server fan panels were installed in each test enclosure. Rear door mount exhaust fan panels were positioned in the same location for the appropriate test.
- Fan positions were the same for all three enclosures, equal to 20 and 30 RU.
- Bottom mount blowers were installed in the 2 - 3 RU position in each enclosure. Bottom mount blowers drew air through identical cutouts in under cabinet floor tiles.
- Rear door mount temperature probes were fixed in the same locations (see page 6) as described above when rear doors were switched from perforated to solid doors.

VI. TEST RESULTS

As discussed above, data was recorded for each cabinet configuration. The tables 3, 4, and 5 in the appendix represent temperatures measured for each test conducted. The complete results tables display temperature differences for the three main enclosure test configurations with similar test variable (Ex: Server Cabinet vs. Equipment Cabinet with Rear Door Mount Server Fan Panels). There are also 2 comparison tables highlighting the differences with door and roof options. (see tables 6 and 7 in the appendix).

See full test results in Appendix. Each probe temperature value is an average of the 3 cabinets.



Figure 7A: This thermal drawing represents the heat dissipation for test 3 with perforated front and rear door and vented roof



Figure 7B: The thermal drawing represents the heat dissipation from test 18 with solid front and rear door with roof fan

VII. ANALYSIS AND CONCLUSIONS

NOTE: When reviewing the data, the reader must consider existing site conditions (i.e. airflow velocity, CRAC discharge temperature, under-floor pressure and other variables) and how they compare to the test site conditions described above.

It is apparent that server enclosures (perforated doors F & R) showed the best thermal performance (see Figure 7A). This was true for 2.1KW and 5.5KW heat loads. With consistent under floor temperatures, pressure and cool air delivery to server intakes, exhaust temperatures to the room were within 10°F of inlet temperatures. **This reduced Delta T provided discharge temperatures from the enclosures that were easily absorbed by the room and well within tolerance for CRAC unit intakes.** Rear door fans and/or bottom mount blowers affected performance, but did not have a significant impact on discharge temperatures. Equipment enclosures with solid front doors (and in some cases solid rear doors) had significantly higher discharge temperatures (see Figure 7B). In these configurations, supplemental fans did have an effect on exhaust temperatures, lowering exhaust temperatures, but not as well as seen in server cabinets. Again, the room was able to accommodate the higher temperatures. However, if many more enclosures had the higher heat loads with these configurations, it might be possible to adversely affect a room's ability to dissipate the heat.

As can be seen when comparing results from 2.1KW and 5.5KW heat loads, that even with these loads almost tripled, discharge temperatures remained fairly consistent. It can be inferred that with a well-designed data center cooling plant, server enclosures are most effective at evacuating and dissipating the increasing heat loads being generated.

Based on these results, and additional experience with large data center design and implementation worldwide, Rittal offers the following recommendations:

Climate Control:

- Maintain Front to Rear Cooling Air Flow Path
- Provide a Hot Aisle/Cold Aisle Orientation
- Place Server Air Intakes as Far Forward as Practical
- Maintain Strict Floor Tile Control
- Limit Number of Cutouts in Floor Tiles Under Cabinets
- Use Supplemental Fans to Reduce or Eliminate Hot Spots in Enclosures
- Install Blanking Panels In ALL Unused Rack Spaces
- Install full height x depth divider panels to segregate equipment clusters

General Enclosures:

- Select A Common Cabinet Configuration (ex: Server)
- Deploy Enclosures by Application (Termination/Network/Server)
- Install The Maximum Footprint (WxD) Possible
- Use Multiple Widths For Various Configurations – Even in a single row
- Group Common Components Together
- And... Make Sure The Doors Are Closed

APPENDIX

THERMAL TESTING RESULTS

Table 3

Server Cabinet: Perforated Doors Front & Rear; Various Fan Options & Floor Tile Configurations

Approx Heat Load: 5500 Watts

| Cabinet Configuration | Test 1 | Test 2 | Test 3 | Test 4 | Test 5 | Test 6 | Test 7 | Test 8 | Test 9 |
|-----------------------|--------|--------|--------|--------|---------------|---------------|--------|--------|--------|
| Front Door | Perf | Perf | Perf | Perf | Perf | Perf | Perf | Perf | Perf |
| Rear Door | Perf | Perf | Perf | Perf | Perf | Perf | Perf | Perf | Perf |
| Roof | Vent | Vent | Vent | Vent | Vent | Vent | Vent | Vent | Vent |
| Floor Tiles | Vent | Solid | Vent | Vent | Vent | Solid | Solid | Vent | Solid |
| Fans | - | - | Rear | Bottom | Rear & Bottom | Rear & Bottom | Bottom | - | - |
| Divider Panels | - | - | - | - | - | - | - | Panels | Panels |

| Temperature Probe Locations | | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | | | | |
|-----------------------------|-----------------------------------|--------------------------------------------------|------|------|------|------|------|------|------|------|
| Air Intake | | | | | | | | | | |
| 1 | Under Floor - In front of Cabinet | 67.4 | 68.0 | 68.0 | 67.4 | 66.8 | 66.2 | 66.8 | 66.2 | 66.2 |
| 2 | Front - Server @5U | 67.4 | 69.3 | 67.4 | 68.0 | 68.0 | 68.0 | 68.6 | 66.8 | 66.2 |
| 3 | Front - Server @12U | 68.7 | 70.5 | 68.7 | 69.2 | 68.0 | 66.8 | 69.8 | 68.0 | 69.8 |
| 4 | Front - Server @20U | 70.5 | 73.0 | 69.3 | 68.6 | 66.2 | 67.4 | 70.4 | 67.4 | 69.2 |
| 5 | Front - Server @25U | 71.1 | 74.3 | 69.3 | 69.3 | 66.8 | 69.2 | 71.6 | 67.4 | 73.4 |
| 6 | Front - Server @30U | 71.8 | 75.5 | 70.5 | 71.7 | 68.7 | 71.6 | 74.6 | 72.8 | 75.2 |
| 7 | Front - Server @35U | 69.9 | 73.3 | 72.0 | 70.4 | 69.5 | 72.1 | 74.4 | 75.2 | 77.6 |
| Air Discharge | | | | | | | | | | |
| 8 | Rear Door - @6U, Center | 72.9 | 73.5 | 73.6 | 75.8 | 79.0 | 77.6 | 77.6 | 71.0 | 71.6 |
| 9 | Rear Door - @21U, Center | 77.7 | 81.3 | 76.5 | 76.4 | 78.5 | 79.4 | 79.4 | 74.6 | 75.2 |
| 10 | Rear Door - @31U, Center | 77.1 | 80.8 | 75.8 | 76.4 | 75.2 | 76.4 | 80.6 | 76.4 | 78.2 |
| 11 | Rear Door - Top, Center | 76.5 | 78.3 | 74.3 | 74.6 | 74.3 | 75.2 | 78.8 | 75.8 | 75.8 |
| 12 | Roof - Center | 76.4 | 75.2 | 73.9 | 72.6 | 73.3 | 74.5 | 77.6 | 75.8 | 76.4 |

Temperature results represent an average of all 3 test cabinets with temperatures recorded at each probe every 2 minutes

Cabinet Configurations:

Test 1: Perf Doors - F & R, Vented Floor Tile - Front

Test 2: Perf Doors - F & R, Solid Floor Tile - Front

Test 3: Perf Doors - F & R, Vented Floor Tile - Front, 2 x Server Fan Panels - Rear Door

Test 4: Perf Doors - F & R, Vented Floor Tile - Front, Bottom Mount Blowers

Test 5: Perf Doors - F & R, Vented Floor Tile - Front, 2 x Server Fan Panels - Rear Door; Bottom Mount Blowers

Test 6: Perf Doors - F & R, Solid Floor Tile - Front, 2 x Server Fan Panels - Rear Door; Bottom Mount Blowers

Test 7: Perf Doors - F & R, Solid Floor Tile - Front, Bottom Mount Blowers

Test 8: Perf Doors - F & R, Vented Floor Tile - Front, Divider Panels

Test 9: Perf Doors - F & R, Solid Floor Tile - Front, Divider Panels

NOTE: All Configurations: Solid Floor Tiles - Rear; Front 19" Rails - 1.5" Off Front Door; Vented Roof

Color Key:

| |
|--------|
| 60-69° |
| 70-79° |
| 80-89° |
| 90-99° |
| 100°+ |



APPENDIX

THERMAL TESTING RESULTS

Table 4

Cabinet: Solid Door - Front, Perf Door - Rear; Various Fan Options, Floor Tile Configurations

Approx Heat Load: 5500 Watts

| Cabinet Configuration | Test 10 | Test 11 | Test 12 | Test 13 | Test 14 | Test 15 | Test 15A | Test 16 |
|-----------------------|---------|---------|---------|---------------|---------|---------|----------|---------------|
| Front Door | Solid | Solid | Solid | Solid | Solid | Solid | Solid | Solid |
| Rear Door | Perf | Perf | Perf | Perf | Perf | Perf | Perf | Perf |
| Roof | Vent | Vent | Vent | Vent | Vent | Vent | Vent | Vent |
| Floor Tiles | Solid | Solid | Solid | Solid | Solid | Solid | Solid | Solid |
| Fans | - | Bottom | Rear | Rear & Bottom | - | Bottom | Rear | Rear & Bottom |
| Divider Panels | - | - | - | - | Panels | Panels | Panels | Panels |

| Temperature Probe Locations | | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | | | |
|-----------------------------|-----------------------------------|--------------------------------------------------|------|-------|------|------|------|------|------|
| Air Intake | | | | | | | | | |
| 1 | Under Floor - In front of Cabinet | 65.6 | 66.2 | 66.8 | 66.2 | 68.0 | 66.2 | 66.8 | 66.8 |
| 2 | Front - Server @5U | 68.0 | 68.6 | 68.6 | 68.6 | 69.8 | 69.2 | 66.8 | 68.6 |
| 3 | Front - Server @12U | 73.4 | 74.6 | 70.4 | 76.4 | 72.8 | 75.2 | 69.2 | 74.6 |
| 4 | Front - Server @20U | 85.4 | 76.4 | 74.6 | 74.0 | 78.8 | 76.4 | 72.8 | 77.6 |
| 5 | Front - Server @25U | 91.4 | 74.0 | 77.6 | 72.8 | 81.8 | 73.4 | 74.6 | 77.6 |
| 6 | Front - Server @30U | 92.6 | 73.4 | 77.0 | 71.6 | 84.8 | 72.8 | 77.6 | 75.2 |
| 7 | Front - Server @35U | 92.0 | 73.4 | 75.8 | 71.6 | 89.0 | 71.6 | 78.8 | 71.0 |
| Air Discharge | | | | | | | | | |
| 8 | Rear Door - @6U, Center | 72.8 | 87.2 | 73.4 | 80.0 | 76.4 | 87.2 | 71.6 | 80.0 |
| 9 | Rear Door - @21U, Center | 92.6 | 84.8 | 101.6 | 96.2 | 85.4 | 85.4 | 93.2 | 87.2 |
| 10 | Rear Door - @31U, Center | 93.2 | 83.0 | 85.4 | 83.6 | 89.0 | 80.0 | 83.0 | 87.2 |
| 11 | Rear Door - Top, Center | 89.6 | 77.0 | 78.2 | 77.0 | 85.4 | 75.2 | 79.4 | 80.0 |
| 12 | Roof - Center | 82.4 | 76.4 | 77.0 | 77.6 | 74.6 | 75.8 | 78.2 | 79.4 |

Temperature results represent an average of all 3 test cabinets with temperatures recorded at each probe every 2 minutes

Cabinet Configurations:

Test 10: Solid Door - Front, Perf Door - Rear

Test 11: Solid Door - Front, Perf Door - Rear; Bottom Mount Blowers

Test 12: Solid Door - Front, Perf Door - Rear; 2 x Server Fan Panels - Rear Door

Test 13: Solid Door - Front, Perf Door - Rear; Bottom Mount Blowers, 2 x Server Fan Panels - Rear Door

Test 14: Solid Door - Front, Perf Door - Rear; Divider Panels

Test 15: Solid Door - Front, Perf Door - Rear; Bottom Mount Blowers, Divider Panels

Test 15A: Solid Door - Front, Perf Door - Rear; 2 x Server Fan Panels - Rear Door; Divider Panels

Test 16: Solid Door - Front, Perf Door - Rear; Bottom Mount Blowers, 2 x Fan Panels - Rear Door; Divider Panels

NOTE: All Configurations: Solid Floor Tiles - Front, Front 19" Rails - 4" Off Front Door; Vented Roof

Color Key:

| |
|--------|
| 60-69° |
| 70-79° |
| 80-89° |
| 90-99° |
| 100°+ |

APPENDIX

THERMAL TESTING RESULTS

Table 5

Cabinet: Solid Door - Front, Solid or Perf Door - Rear; 2 x 550cfm Roof Mount Fans, Solid Floor Tiles, with or w/o Bottom Mount Blowers

Approx Heat Load: 5500 Watts

| Cabinet Configuration | Test 17 | Test 17A | Test 18 | Test 18A | Test 19 | Test 19A | Test 20 |
|-----------------------|---------|----------|---------|----------|---------|----------|--------------|
| Front Door | Solid | Solid | Solid | Solid | Solid | Solid | Partial vent |
| Rear Door | Solid | Perf | Solid | Perf | Solid | Perf | Solid |
| Roof | Fan | Fan | Fan | Fan | Fan | Fan | Fan |
| Floor Tiles | Solid | Solid | Solid | Solid | Solid | Solid | Solid |
| Fans | - | - | - | - | Bottom | Bottom | - |
| Divider Panels | Panels | Panels | - | - | - | - | - |

| Temperature Probe Locations | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | | | |
|-----------------------------|--------------------------------------------------|--|--|--|--|--|--|--|
|-----------------------------|--------------------------------------------------|--|--|--|--|--|--|--|

| Air Intake | | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | | | |
|---------------|-----------------------------------|--------------------------------------------------|------|-------|------|-------|------|------|--|
| 1 | Under Floor - In front of Cabinet | 65.0 | 68.0 | 66.2 | 68.0 | 66.2 | 66.2 | 67.4 | |
| 2 | Front - Server @5U | 67.4 | 71.0 | 67.4 | 69.2 | 70.4 | 69.8 | 66.8 | |
| 3 | Front - Server @12U | 69.8 | 74.6 | 70.4 | 72.2 | 77.6 | 77.0 | 68.6 | |
| 4 | Front - Server @20U | 71.6 | 77.6 | 73.4 | 76.4 | 78.2 | 78.8 | 69.8 | |
| 5 | Front - Server @25U | 71.0 | 81.2 | 76.4 | 79.4 | 79.4 | 79.4 | 71.0 | |
| 6 | Front - Server @30U | 77.6 | 84.2 | 81.2 | 84.2 | 82.4 | 78.2 | 74.0 | |
| 7 | Front - Server @35U | 80.6 | 86.0 | 81.2 | 83.6 | 79.4 | 73.4 | 73.4 | |
| Air Discharge | | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | | | |
| 8 | Rear Door - @6U, Center | 69.8 | 74.0 | 69.2 | 73.4 | 100.4 | 76.4 | 80.6 | |
| 9 | Rear Door - @21U, Center | 102.8 | 85.4 | 101.6 | 84.8 | 99.8 | 92.6 | 99.8 | |
| 10 | Rear Door - @31U, Center | 93.8 | 80.6 | 93.8 | 81.8 | 96.2 | 84.8 | 90.8 | |
| 11 | Rear Door - Top, Center | 90.8 | 82.4 | 90.8 | 83.0 | 94.4 | 80.6 | 89.0 | |
| 12 | Roof - Center | 84.8 | 80.0 | 87.2 | 81.2 | 84.2 | 80.6 | 88.4 | |

Temperature results represent an average of all 3 test cabinets with temperatures recorded at each probe every 2 minutes

Cabinet Configurations:

Test 17: Solid Doors - Front & Rear; 2 x 550cfm Roof Mount Fans, Divider Panels

Test 17A: Solid Door - Front, Perf Door - Rear; 2 x 550cfm Roof Fans, Divider Panels

Test 18: Solid Doors - Front & Rear; 2 x 550cfm Roof Mount Fans

Test 18A: Solid Door - Front, Perf Door - Rear; 2 x 550cfm Roof Fans

Test 19: Solid Doors - Front & Rear; 2 x 550cfm Roof Mount Fans, Bottom Mount Blowers

Test 19A: Solid Door - Front, Perf Door - Rear; 2 x 550cfm Roof Fans, Bottom Mount Blowers

Test 20: Partial Vented View Door - Front, Solid Door - Rear; 2 x 550cfm Roof Fans

NOTE: All Configurations: Solid Floor Tiles - Front, Front 19" Rails - 4" Off Front Door; Solid Roof w/fans

Color Key:

| |
|--------|
| 60-69° |
| 70-79° |
| 80-89° |
| 90-99° |
| 100°+ |



APPENDIX

THERMAL TESTING COMPARISON

Table 6

Cabinet: Perforated Doors (F&R) vs. Solid Door (F) & Perf Door (R)

Approx Heat Load: 5500 Watts

| Cabinet Configuration | Test 1 | Test 10 | Test 3 | Test 12 | Test 4 | Test 11 | Test 5 | Test 13 |
|-----------------------|--------|---------|--------|---------|--------|---------|---------------|---------------|
| Front Door | Perf | Solid | Perf | Solid | Perf | Solid | Perf | Solid |
| Rear Door | Perf | Perf | Perf | Perf | Perf | Perf | Perf | Perf |
| Roof | Vent | Vent | Vent | Vent | Vent | Vent | Vent | Vent |
| Floor Tiles | Vent | Solid | Vent | Solid | Vent | Solid | Vent | Solid |
| Fans | - | - | Rear | Rear | Bottom | Bottom | Rear & Bottom | Rear & Bottom |
| Divider Panels | - | - | - | - | - | - | - | - |

| Temperature Probe Locations | | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | | | |
|-----------------------------|-----------------------------------|--------------------------------------------------|------|------|-------|------|------|------|------|
| Air Intake | | | | | | | | | |
| 1 | Under Floor - In front of Cabinet | 67.4 | 65.6 | 68.0 | 66.8 | 67.4 | 66.2 | 66.8 | 66.2 |
| 2 | Front - Server @5U | 67.4 | 68.0 | 67.4 | 68.6 | 68.0 | 68.6 | 68.0 | 68.6 |
| 3 | Front - Server @12U | 68.7 | 73.4 | 68.7 | 70.4 | 69.2 | 74.6 | 68.0 | 76.4 |
| 4 | Front - Server @20U | 70.5 | 85.4 | 69.3 | 74.6 | 68.6 | 76.4 | 66.2 | 74.0 |
| 5 | Front - Server @25U | 71.1 | 91.4 | 69.3 | 77.6 | 69.3 | 74.0 | 66.8 | 72.8 |
| 6 | Front - Server @30U | 71.8 | 92.6 | 70.5 | 77.0 | 71.7 | 73.4 | 68.7 | 71.6 |
| 7 | Front - Server @35U | 69.9 | 92.0 | 72.0 | 75.8 | 70.4 | 73.4 | 69.5 | 71.6 |
| Air Discharge | | | | | | | | | |
| 8 | Rear Door - @6U, Center | 72.9 | 72.8 | 73.6 | 73.4 | 75.8 | 87.2 | 79.0 | 80.0 |
| 9 | Rear Door - @21U, Center | 77.7 | 92.6 | 76.5 | 101.6 | 76.4 | 84.8 | 78.5 | 96.2 |
| 10 | Rear Door - @31U, Center | 77.1 | 93.2 | 75.8 | 85.4 | 76.4 | 83.0 | 75.2 | 83.6 |
| 11 | Rear Door - Top, Center | 76.5 | 89.6 | 74.3 | 78.2 | 74.6 | 77.0 | 74.3 | 77.0 |
| 12 | Roof - Center | 76.4 | 82.4 | 73.9 | 77.0 | 72.6 | 76.4 | 73.3 | 77.6 |

Temperature results represent an average of all 3 test cabinets with temperatures recorded at each probe every 2 minutes

Cabinet Configurations:

Test 1: Perf Doors - F & R, Vented Floor Tile - Front

Test 10: Solid Door - Front, Perf Door - Rear

Test 3: Perf Doors - F & R, Vented Floor Tile - Front, 2 x Server Fan Panels - Rear Door

Test 12: Solid Door - Front, Perf Door - Rear, 2 x Server Fan Panels - Rear Door

Test 4: Perf Doors - F & R, Vented Floor Tile - Front, Bottom Mount Blowers

Test 11: Solid Door - Front, Perf Door - Rear, Bottom Mount Blowers

Test 5: Perf Doors - F & R, Vented Floor Tile - Front, 2 x Server Fan Panels - Rear Door, Bottom Mount Blowers

Test 13: Solid Door - Front, Perf Door - Rear, Bottom Mount Blowers, 2 x Server Fan Panels - Rear Door

Color Key:

| |
|--------|
| 60-69° |
| 70-79° |
| 80-89° |
| 90-99° |
| 100°+ |

APPENDIX

THERMAL TESTING COMPARISON

Table 7

Server Cabinet: Vented Roof vs. Roof Mount Fans

Approx Heat Load: 5500 Watts

| Cabinet Configuration | Test I | Test I0 | Test I8A | Test 4 | Test I1 | Test I9A |
|-----------------------|--------|---------|----------|--------|---------|----------|
| Front Door | Perf | Solid | Solid | Perf | Solid | Solid |
| Rear Door | Perf | Perf | Perf | Perf | Perf | Perf |
| Roof | Vent | Vent | Fan | Vent | Vent | Fan |
| Floor Tiles | Vent | Solid | Solid | Vent | Solid | Solid |
| Fans | - | - | - | Bottom | Bottom | Bottom |
| Divider Panels | - | - | - | - | - | - |

Temperature Probe Locations | Average Temperature of 3 cabinets - ° Fahrenheit

| Air Intake | | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | |
|---------------|-----------------------------------|--------------------------------------------------|------|------|------|------|------|
| 1 | Under Floor - In front of Cabinet | 67.4 | 65.6 | 68.0 | 67.4 | 66.2 | 66.2 |
| 2 | Front - Server @5U | 67.4 | 68.0 | 69.2 | 68.0 | 68.6 | 69.8 |
| 3 | Front - Server @12U | 68.7 | 73.4 | 72.2 | 69.2 | 74.6 | 77.0 |
| 4 | Front - Server @20U | 70.5 | 85.4 | 76.4 | 68.6 | 76.4 | 78.8 |
| 5 | Front - Server @25U | 71.1 | 91.4 | 79.4 | 69.3 | 74.0 | 79.4 |
| 6 | Front - Server @30U | 71.8 | 92.6 | 84.2 | 71.7 | 73.4 | 78.2 |
| 7 | Front - Server @35U | 69.9 | 92.0 | 83.6 | 70.4 | 73.4 | 73.4 |
| Air Discharge | | Average Temperature of 3 cabinets - ° Fahrenheit | | | | | |
| 8 | Rear Door - @6U, Center | 72.9 | 72.8 | 73.4 | 75.8 | 87.2 | 76.4 |
| 9 | Rear Door - @21U, Center | 77.7 | 92.6 | 84.8 | 76.4 | 84.8 | 92.6 |
| 10 | Rear Door - @31U, Center | 77.1 | 93.2 | 81.8 | 76.4 | 83.0 | 84.8 |
| 11 | Rear Door - Top, Center | 76.5 | 89.6 | 83.0 | 74.6 | 77.0 | 80.6 |
| 12 | Roof - Center | 76.4 | 82.4 | 81.2 | 72.6 | 76.4 | 80.6 |

Temperature results represent an average of all 3 test cabinets with temperatures recorded at each probe every 2 minutes

Cabinet Configurations:

Test I: Perf Doors - F & R, Vented Floor Tile - Front

Test I0: Solid Door - Front, Perf Door - Rear

Test I8A: Solid Door - Front, Perf Door - Rear; 2 x 550cfm Roof Fans

Test 4: Perf Doors - F & R, Vented Floor Tile - Front, Bottom Mount Blowers

Test I1: Solid Door - Front, Perf Door - Rear; Bottom Mount Blowers

Test I9A: Solid Door - Front, Perf Door - Rear; 2 x 550cfm Roof Fans, Bottom Mount Blowers

Color Key: 60-69°

70-79°

80-89°

90-99°

100°+



Rittal Corporation
One Rittal Place • Springfield, OH 45504
Tel: (937) 399-0500 • Fax: (937) 390-5599
Toll Free: 1-800-477-4000
Email: rittal@rittal-corp.com
Internet: www.rittal-corp.com